

Don Ross Arena Ice Plant RFP

ADDENDUM #3

Dear Proponents,

The above referenced Request for Proposal is modified as described hereunder. You are requested to incorporate these changes into your quotation. All other Terms and Conditions stated in the original RFP remain unchanged and apply in full to this Addendum.

Acceptable option for Condenser Dry Run

RE: SCOPE OF WORK

- 4) The City has identified the following components / specifications that must be a part of the new ice plant:
 - b) The condenser is to be adiabatic type sized accordingly for plant operation in all weather conditions. Dry operation to be a minimum 45 degrees Fahrenheit

ADDENDUM: The City will accept the dry operation as low as 36 Degrees Fahrenheit

RE: SCOPE OF WORK

- 4) The City has identified the following components / specifications that must be a part of the new ice plant:
 - g) According to our research, to meet our operating objectives we will require the following:
 - v) 78 wet bulb, 72 dry bulb

ADDENDUM: Wet and dry bulb settings to be in accordance with Saskatoon industry standard wet / dry bulb standards.

END OF ADDENDUM # 3