Project 25-15 - City of North Battleford Mike Lepp 445-1753 Cell 480-7898 **Building Name**; Don Ross Center

Building No. 03
N. Battleford, SK

Page 5

Date: June 18, 2025

	Date: Julie 16, 2023								
Sample No.	Location in Building	Sample Type	Sample Descripton	Phase Percent of Total	Asbestos Content ?	Other parts of This Phase			
	Basement W	<u> </u> /ashroom (By R	Room 104)						
DR-36			Brown Paper	2 + 2	ND	100% Cellulose			
			Off-white Cementicious	96	ND	100% NF			
DR-37	DR-37 East Wall		Paint	2	ND	100% NF			
		Drywall Mud	White, Cementicious	98	ND	100% NF			
DR-38A	West Wall	Plaster	Grey Paint	2	ND	100% NF			
		Joint Compund	Grey, Cementicious	98	ND	100% NF			
DR-38B	same	Plaster	Grey, Cementicious	100	ND	100% NF			
		Skim Coat							
DR-38C	same	Plaster	Beige, Cementicious	100	ND	<1% Horse Hair, 99% NF			
		Base Coat							
		om (in Washro	,						
DR-39A	South Wall	Plaster	Green Paint	5	ND	100% NF			
		Skim Coat	White, Cementicious	96	ND	100% NF			
DR-39B	same	Plaster	White/Gold, Cementicious	100	ND	<1% Actinolite, >99% NF			
		Base Coat 1							
DR-39C	same	Plaster	Grey, Cementicious	100	ND	100% NF			
		Base Coat 2							
DR-40	Floor Tile	Floor Tile	White, Blue Flecks, Vinyl	100	ND	100% NF			
		12" x 12"							
	Room 104								
DR-41	Ceiling	Texture	White Paint	5	ND	100% NF			
			Grey, Cementicious	95	YES	7% Chrysotile, 93% NF			
	<u> </u>	<u> </u>							

R. S. MANAGEMENT SERVICES INC. Project 25-06 - City of N.B Lead Paint Samples Attn; Mike Lepp						os Consulting & Management	CERTIFICATE OF ANALYSIS Spreadsheet				
						Building Name; Don Ross Center 891 - 99th Street North Battleford, SK					
Sample No.	Location	Sampled item	Color Top Paint layer	Color Middle Paint Layer	Color Bottom Layer	Sample Descripton	Lead Content ?	Description of Results Found			
	Basement W	l /ashroom by	⊥ / Room 10₄	<u> </u> 4							
DR-01	Bottom of	White	White			Paint Lifted off	YES	200 ugm/gm			
	Bulkhead	Paint				of surface		<u> </u>			
DR-02	Inside of	Grey	Grey			Paint Lifted off	YES	1,300 ugm/gm			
	Bulkhead	Paint				of surface		, , , , , , , , , , , , , , , , , , , ,			
	_				<u> </u>						
	Recommend NO dry scraping without appropriate PPE. Dry scraping should have encosure or drop sheets or both.										
	+		e encosure or drop sneets or b nended (IF removal is required			T					
	MUST provid				<u>' </u>						
	Sandblasting										
	Carrabiasarig										
	Due to the ar	nount of plas	ter and dry	wall, the Cor	an expect dust. Just n	ot from the	paint.				
	Allowable Lin	nit as per Ca									
	Allowable Limit as per Canadian Hazardous Products Act = 90 ug/gram										

Sask. Limits apply to Airborne content during removals